

## PACKAGING PLANT LONGVIEW, WA

### BY THE NUMBERS



#### PROJECT FACTS

Location: **Longview, Washington**  
Type: **Packaging manufacturing facility**



#### MAXIM FACTS

Project Duration: **Less than one week**  
Total Contractors: **1**



#### CRANE STATS

- **Grove GMK 7550 All-Terrain Crane with 101-foot luffing jib, MegaWing configuration and 308,600 pounds of counterweight**
- **Grove GMK 5165-2 All-Terrain Crane with 62,800 pounds of counterweight**
- **Two Scheuerle six-axle SPMTs**

## MAXIM GETS PACKAGING PLANT UP AND RUNNING AGAIN

*Crucial Heavy Manufacturing Equipment Required  
Skillful Lifting and Heavy Haul Expertise*

**THE PROJECT:** Located north of Portland, Oregon, a packaging plant needed to urgently replace a conveyor system that went down. Fortunately, the company had spare conveyor equipment onsite that could be used to resume manufacturing. However, the 65,000-pound pieces had to be carefully moved more than a mile to be staged for reassembly.

The scope and scale of this project required experience with comprehensive lift solutions and heavy haul projects that only a company with Maxim's resources could provide.

**EQUIPMENT:** For this project, Maxim provided two Grove AT cranes (550-ton and 165-ton) and two 6-axle Scheuerle Self Propelled Modular Transporter (SPMT) to move four conveyor pieces each weighing more than 65,000 pounds. Maxim's eight-person crew included two crane operators, two oilers and four working the SPMT. The crew used extreme care to work in the tight quarters of the manufacturing facility.

**RESULTS:** A successful lift and move of the equipment in less than a week - the project was completed ahead of schedule.

*Photos by Ole Pedersen*

